No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
10	Providing and fixing R.C. ventilators as per design	S.ft.	1 4 0	105	
11	Providing and fixing R.C.C. chajja 3′ to 4½′ in projection as per design and specification, etc., complete including anchoring	,,	0 12 0	1,233	
12	Providing and fixing including hoisting Tata's tested girders on B.S.S., etc., complete	Cwt.	18 0 0	668·3	
13	Providing R.C. roofing with spans of 7′ to 10′ including cantilever projection of 3′—6″ with ceiling of lime mortar plaster and top finished with koppi to 3″ to 6″, three corners of flat tiles, water proof course and mortar plastered	Sqr.	80 0 0	170	
14	Chunam plastering, stone walls corners rounded inside (machine-ground)	,,	4 8 0	150	
15	White washing, two coats	,,	0 4 6	150	
16	Cement mortar 1 : 3 plastering for window cills 1″ thick	,,	8 0 0	1·5	
17	Cement pointing with 1 : 3 cement mortar, lines cut as per design to ¾″ deep	,,	4 8 0	164	
18	Providing and fixing ornamental C.I. hand railings 2¼′ height as per design, etc., complete including two coats of painting.	R.ft.	2 0 0	221	
19	Varnishing, two coats	Sqr.	4 0 0	22	
20	Green silicate painting, two coats	,,	4 0 0	1·5	
21	Boxing rolled steel girders with brick in mortar and lime plastered	R.ft.	1 0 0	1,069	
22	Constructing parapet wall 3′ height including blocking courses ; ballustrades and capital, chunam plastering, white washed, colour washed, etc., complete as per design	,,	2 0 0	60	
23	Providing and fixing cast iron downpour pipes 4½″ diameter	,,	1 8 0	628	
24	Providing and fixing wooden stair case to the roof as per design, etc.	L. S.	....	....	
25	Decorative architectural finishes	,,	....	5,000	

D. A. HUKERI,
Executive Engineer.

ANJANAPUR DIVISION.

Tender Notification dated 23rd February 1940.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Anjanapur Division, up to 12 NOON on 1st April 1940, for construction of a Circle of 100 feet diameter at entrance to waste weir of Anjana ur Reservoir, Shikar ur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Anjanap r between the hours of 8 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Eng neer on payment of As. 4 per form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treas ry Challan for Rs. 140 credited to "17 (a) Public Works Deposits" as earnest money ,and superscribed "Tender for construction of a Cir le of 100 feet diameter at entrance to waste weir of Anjanapur Re ervoir, Shikarpur Taluk," in default of which the tender will be rejected.

5. The final acceptance of a .y tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tenders or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board, in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

10. Rates once tendered will not be enhanced on any account.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any tender tendered at so much percentage less or more than estimated rate will not be accepted.

13. The tenderer is bound to employ local labour as far as possible.

14. Chamundy cement of approved quality should be used.

Abstract estimate for construction of a circle of 100 feet diameter at entrance to waste weir of Anjanapur Reservoir, Shikarpur Taluk.

No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
				Rs. a. p.	Rs. a. p.
1	Earthwork embankment with watering, tamping and consolidation complete with an approximate lead of 2 furlongs to be formed in 9″ layers ..	C.yd.	1,469		
2	Earthwork excavation for foundation of circle wall	,,	15		
3	Concrete broken stone jelly in cement mortar (1 : 4 : 8) for foundation	C.ft.	382		
4	Burnt brick in cement mortar for foundation, basement and superstructure (1 : 4) ..	,,	555		
5	Burnt brick in cement mortar 1 : 4 arch work including centering, etc., complete	,,	25		
6	Ornamental finials on top of entrance pillars "A" as per design	Each	2		
7	R.C.Concrete Architrave on top of entrance gate (width 4½ feet) (1 : 2 : 4 with suitable reinforcement)	C.ft.	59		
8	Plain parapet. Brick in mortar as per design on top of gateway including plastering, etc., complete with stucco work as per design	R.ft.	12		
9	Cement concrete parapet wall alround the circle as per design pillars 6″×6″×2⅝ feet high as per specifications	C.ft.	352		
10	Providing and fixing inscription slabs 4′×3′×4″ and 3′×2′×4″ with cement mortar bands, cornice, etc., tablets at site	Each	2		
11	Removing and refixing the existing tablet with cement mortar bands, cornice, etc., in brick masonry	L. S.	2		
12	Stoccu work—rough cement plastering with pebbles stuck in (to give stone facing false appearance)	Sqr.	22·5		
13	Providing and fixing wall fountains as per design with 300 R.ft. of ½″ G. I. pipe and necessary fittings, etc., complete	L. S.	..		
14	Providing R.C.C. benches as per design ..	Each	8		
15	Cement concrete curbs	R.ft.	336		
16	Providing and fixing ornamental lamp post at centre	L. S.	..		
17	Forming car-drive roadway including watering, tamping, consolidation, gravelling and sand blindage, etc., complete	S.yd.	428		
18	Turfing	S.yd.	817		
19	Painting centre lamp post with Alluminium white or Zinc white paint	L. S.	..		

M. V. KRISHNASWAMY IYENGAR,
Executive Engineer.